



WORK AREA



EXTENT OF EXTERNAL SCAFFOLDING & HOARDING



EXTENT OF INTERNAL SCAFFOLDING

NORTH CLERESTORY



SCAFFOLDING LIFT
  GUTTERS / DOWNPIPES
  CLERESTORY ASHLAR
  CLERESTORY WINDOWS

GENERAL NOTES

Ground, gravestones, roofs, all to be protected prior to erection of scaffolding. A set of dilapidation photos will be provided before commencing works.

All work areas will be made good on completion.

SCHEDULED WORKS

Please see attached schedule of works.

WORKS DESCRIPTION

Clearance of gutters and downpipes.

Repointing of open or failed joints to clerestory ashlar.

Repair of leaded lights and associated metalwork to clerestory windows.

MATERIAL SPECIFICATION

**Mortars**  
Lime based mortar nominally 3:1 with mixture of Brynkir and Mersey sands and stonedust to achieve appropriate aesthetic match to existing pointing mortar (as per previous phase of work to Tower by Recclesia).

**Glass**  
Mouth blown cylinder glass to be used for any infill or stop gaps to leaded lights.

**Lead**  
Milled British lead came to matching imperial dimensions and profile.

Leaded Light Cement  
Hodgsons Phoenix



Unit 3 St Ives Way Chester CH5 2QS - 01244 906002  
Unit 6 Agecroft Ind Est, Manchester M27 8WA - 0161 6676550  
www.recclesia.com

FARNDON PARISH CHURCH - ST CHAD'S

NORTH CLERESTORY WORKS

SK3786-01 V2 JM 09-10-22

NTS

ISSUED FOR APPROVAL